	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
162	67.50	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) Qty Upto 125%	Rmtr	1338.25	Rupees One Thousand Three Hundred Thirty Eight and Twenty Five Paise Only
	45.50	Qty Above 125%	Rmtr	1338.25	Rupees One Thousand Three Hundred Thirty Eight and Twenty Five Paise Only
163	12.00	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications. - 250mm dias.	Rmtr	2158.62	Rupees Two Thousand One Hundred Fifty Eight and Sixty Two Paise Only
164	1.25	Providing 175mm dia ms casing cap Qty Upto 125%	No	101.00	Rupees One Hundred One Only
	0.75	Qty Above 125%	No	101.00	Rupees One Hundred One Only
165	1.25	Providing MS Casing pipe collars Qty Upto 125%	No	151.50	Rupees One Hundred Fifty One and Fifty Paise Only
	0.75	Qty Above 125%	No	151.50	Rupees One Hundred Fifty One and Fifty Paise Only
166	0.00	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings .	Unit	0.00	0.00
167	0.00	KSRB13-6: Providing and fixing to wall celling and floor glavanised/ mild steel tubes (medium grade 1.27 kg /mt) B class 50 mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications.	Mtr	0.00	0.00

Executive Engineer
Project Division
Yelahanka Zone

Contractor

	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
168	133.05	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and Powder coated extrued PVC sheathed suitable for working voltage upto 1100 Volts as per IS - 694 ; 1990 AND CONFORMING TO gtp OFGROUP A	Mtr	207.05	Rupees Two Hundred Seven and Five Paise Only
169	0.00	Labour charges for erection of new/ repaired submersible pumpset along with gi pipes inculding transportion each length	No	0.00	0.00
170	1.00	Supplying and flush polished wood board with out front frount plank made of not less than 15mm thick plank after due groove cutting Finishing with necessary on fixing the same to the wall using tapered inverted wooden plugs screws etc.	Each	294.92	Rupees Two Hundred Ninety Four and Ninety Two Paise Only
171	35.00	Supplying of 1.1 KV LT UG cable having aluminium condutor PVC insulated shethed, EXTREDED INNER SHEATHRD galvnised steel,stirp confirming IS 3975;1990 AND extruded PVC outer sheathing armoured cable IS 1554 part 1;1998 and confirming to GTP of group.	Mtr	141.80	Rupees One Hundred Forty One and Eighty Paise Only
172	35.00	Labour charges for laying of 1.1 K.V class UG cable, P No. 41 / I No. 6.5.1 In existing trencg/duct 6Sqmm to 16 Sqmm)	Mtr	12.00	Rupees Twelve Only
173	32.00	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc., complete	Mtr	114.13	Rupees One Hundred Fourteen and Thirteen Paise Only
174	2.00	Supplying and fixing of Class A (medium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class	Mtr	338.35	Rupees Three Hundred Thirty Eight and Thirty Five Paise Only
175	1.00	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.,	NO	272.70	Rupees Two Hundred Seventy Two and Seventy Paise Only
176	1.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia,	NO	3029.70	Rupees Three Thousand Twenty Nine and Seventy Paise Only
177	3.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete....	Each	352.49	Rupees Three Hundred Fifty Two and Forty Nine Paise Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
178	6.00	Supplying and fixing of heavy duty glands for ug cable 1.1 kv etc., complete....	Each	84.84	Rupees Eighty Four and Eighty Four Paise Only
179	1.00	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 32 amps triple pole with all lead and lift, loading, unloading and labour charges etc complete as per specifications	Each	1349.36	Rupees One Thousand Three Hundred Forty Nine and Thirty Six Paise Only
180	1.00	Supply and Installation / Fixing / Provision of Outdoor type Thermoplastic Modular Panel enclosure with transparent Polycarbonate Lid, shock proof, IP65 (Weather Proof), rust proof, dust proof, water proof, corrosion proof having internally Embedded gasket on both lid and flap suitable to fix Single Phase / Three Phase Energy Meter in suitable base plate and having a provision for Fuse / MCB cutout with suitable transparent hinged flap opening for operating MCB along with complete tamper proof SEALING facility.	Each	12201.81	Rupees Twelve Thousand Two Hundred One and Eighty One Paise Only
181	1.00	KSRB 13-7.1-5: Providing and fixing in position 65mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications	NOS	1797.64	Rupees One Thousand Seven Hundred Ninety Seven and Sixty Four Paise Only
182	2.00	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.	Each	218.46	Rupees Two Hundred Eighteen and Forty Six Paise Only
183	2.00	Gate value 65mm nominal bore gun metal	NOS	1711.87	Rupees One Thousand Seven Hundred Eleven and Eighty Seven Paise Only
184	1.00	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset. PRED Bangalore Circle SE Approved Date 30.07.2010 12.5HP to 30 HP Star Delta Starter	No	10100.00	Rupees Ten Thousand One Hundred Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
185	0.00	Earth work excavation By Manuall Means for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches, 1.5m and above in width, in Soft rock/ ordinary rock not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with all lead upto 50m after breaking of clods complete as per specifications.	Cum	0.00	0.00
186	0.00	Filling the Foundation Trenches using approved Sand as per Drawing & Technical Specification in 250mm layers, Whereever necessary watering and ramming including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications Morth Chapter 12.	Cum	0.00	0.00
187	0.00	KSRB13-9.4 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 63mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification	Rmtr	0.00	0.00
188	0.00	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	0.00	0.00
189	0.00	KSRRB M300-1. Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. MORTH / Chapter 3	Cum	0.00	0.00
190	0.00	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. MORTH Specification No. 2100	Cum	0.00	0.00
191	0.00	KSRRB M2200-5.9. Providing and laying Design mix M20 with OPC @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.46cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 including cost of materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. - i) Upto 5 m height.	Cum	0.00	0.00

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Sl No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
192	0.00	KSRRB M400-19. Construction of Median and island above road level with approved material deposited from borrowpits, spread, sloped and compacted as per Clause 400.7 complete as per specifications. MORTH Specification No.407	cum	0.00	0.00
193	0.00	KSRRB M400-17: Providing, laying, spreading and compacting graded stones aggregate to Wet Mix Macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mix method of tipper to site,Laying in uniform layers with paver in subbase/base course on the well prepared surface and compacting with vibratory rollers to achive the desired density complete as per MORTH specification No. 406.etc with all lead and lifts and as per directions of the Engineer-in-charge	cum	0.00	0.00
194	0.00	Providing and laying/fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick for flooring conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification.	Sqm	0.00	0.00
195	122.50	Providing and fixing pre cast solid cement concrete kerb stones made out of C.C. 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc., complete. Qty Upto 125%	No.	436.80	Rupees Four Hundred Thirty Six and Eighty Paise Only
	183.50	Qty Above 125%	No.	436.80	Rupees Four Hundred Thirty Six and Eighty Paise Only
196	19.25	KSRRB 800-1. Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Qty Upto 125%	Sqm	85.65	Rupees Eighty Five and Sixty Five Paise Only
	28.86	Qty Above 125%	Sqm	85.65	Rupees Eighty Five and Sixty Four Paise Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

Sl No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
197	2.00	Supply & fixing of Pull Down Challenger : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our	Unit	298960.00	Rupees Two lakh Ninety Eight Thousand Nine Hundred Sixty Only
198	2.00	Supply & fixing of Seated Chest Press : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Unit	290375.00	Rupees Two lakh Ninety Thousand Three Hundred Seventy Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
199	2.00	Supply & fixing of Self Weighted Rower : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our	Unit	208312.50	Rupees Two lakh Eight Thousand Three Hundred Twelve and Fifty Paise Only
200	2.00	Supply & fixing of Rider : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns.	Unit	113625.00	Rupees One lakh Thirteen Thousand Six Hundred Twenty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
201	1.00	Supply & fixing of Bicycle : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns	Unit	157812.50	Rupees One lakh Fifty Seven Thousand Eight Hundred Twelve and Fifty Paise Only
202	1.00	Supply & fixing of Arm & Pedal Bike : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Unit	214625.00	Rupees Two lakh Fourteen Thousand Six Hundred Twenty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
203	1.00	Supply & fixing of Tai Chi Spinners : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Unit	145187.50	Rupees One lakh Forty Five Thousand One Hundred Eighty Seven and Fifty Paise Only
204	1.00	Supply & fixing of Big Shoulder Wheel : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Unit	157812.50	Rupees One lakh Fifty Seven Thousand Eight Hundred Twelve and Fifty Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Sl. No.	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
205	1.00	Supply & fixing of HD Double Health Walker. All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance	Unit	298960.00	Rupees Two lakh Ninety Eight Thousand Nine Hundred Sixty Only
206	1.00	Supply & fixing of HD Sit Up Station : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Unit	157812.50	Rupees One lakh Fifty Seven Thousand Eight Hundred Twelve and Fifty Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Sl No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
207	1.00	Supply & fixing of HD Squat Pushing : All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out a minimum of 100 public park projects in India with EN16630-GS certified products either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory during technical bid. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the	Unit	271437.50	Rupees Two lakh Seventy One Thousand Four Hundred Thirty Seven and Fifty Paise Only
208	2.00	Supply & fixing of HD Waist Twister :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance	Unit	164125.00	Rupees One lakh Sixty Four Thousand One Hundred Twenty Five Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
209	2.00	Supply & fixing of HD Mini Ski :All products must tested and certified to meet EN16630 safety standards with GS test mark. The EN16630 certificates must be issued by a reputed notified International Certifying Body such as IPEMA, TUV, CPSC, or SGS only. The GS mark-EN 16630 certificates must be in the name of a supplier who has carried out in excess of at least 50 public park projects in India either by themselves or through their dealers or contractors. These EN16630 & GS Mark certificates must be clearly displayed on the notified certifying bodies websites as online verification is mandatory. All products must clearly display the GS mark as has been issued in the EN16630 safety certificates. All Tubular steel of 2.5mm thickness are galvanized and zinc dipped. Joints are Robotic Welded. All welded joints are scalloped as necessary and welded to an approved MIG process. All welds are dressed off removing all sharp edges & burrs. Zinc Primer paint is applied at all the welding paints prior to finishing. All metal parts are powder coated using AKZO Nobel - Great Wall Powder to the thickness of 80 - 120 microns. All metal parts are tested in our salt spray machine that uses a 5% NaCL solution in accordance to	Unit	201091.00	Rupees Two lakh One Thousand Ninety One Only
210	157.74	Supply and fixing of single skin kalzip roofing systems of 65/400, 0.9mm thick Aluminium standing seam roof sheets. The sheets comprise of Profiled sheeting of Aluminium self-supported standing seam roof system manufactured from Aluminium alloy AA 3004, minimum material thickness of 0.9mm and PVDF finishing RAL 9006 on the exposed surface with ST clips and necessary accessories. Structure: (i) Supplying, cutting, bending and fabricating hot rolled plates, sag rods, brackings and connection bolts to form a column, truss with base plates and purlins. (ii) Erection of the above truss work structure at required height. (iii) Providing and applying one coat of red oxide primer and two coats of synthetic enamel paint. The scope of work includes a) Design, Engineering, Fabrication and erection of steel structure, roof sheeting and facade system. b) Supply and installation of flashing, capping, screws and all other necessary accessories.	Sqm	15175.25	Rupees Fifteen Thousand One Hundred Seventy Five and Twenty Five Paise Only
211	0.00	Bescom Deposit for Borewell	LS	0.00	0.00
E1	32.04	Providing and Fixing pre cast covering Slab 230mm thick made out of CC , Jelly 20mm Down Size with steel reinforcement including form work, curing, including cost of all materials, labour, hire charges of machinery, loading, unloading, lead and lift, transportation etc, complete and as per the directions of the Engineer-in-charge of the work	Sqm	5087.37	Rupees Five Thousand Eighty Seven and Thirty Seven Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

Item No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
E2	13.50	Providing and laying in position Reinforced cement concrete for all Sub structures of building, Irrigation works, Sub structure works of bridges, Drain works & other parallel works from 0.50m to 3.50 m height. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necesary, including all lead & lifts, cost of all materials of quality, confirming to the requirements of relevant IS codes, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications.(The cost of steel reinforcement & formwork to be paid separately) M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates	Cum	6630.45	Rupees Six Thousand Six Hundred Thirty and Forty Four Paise Only
E3	258.71	Construction of Embankment by excavating the available approved Gravel/Murrum deposited at a place or borrow pits during or prior excavation with all lifts and lead, transportation to site, spreading, grading to required slope and compacting to meet the requirement complete as per specifications, including cost of labour,rolling,water,all materials, usage& all other appurtenaces required to complete the work.	Cum	446.62	Rupees Four Hundred Forty Six and Sixty Two Paise Only
E4	100.00	40mm Normal gauge polythene bore pipes	Mtr	75.75	Rupees Seventy Five and Seventy Five Paise Only
E5	1.00	Supply, installing,testing and commissioning COMMON control panelconsisting of the following INCOMING:1 No set of Phase indicating lamps with SFU of suitable rating 1 No, Analog Ammeter, 1 No Analog Voltmeter 1ni with Phase selector switch, Isolating switch OUTGOING for Main Electrical Pump: 1 No. MCB 1 No. DOL of S/D Starter suitable for respective HP 1 No. Electrcal Protection Like single Phase preventor, under voltage over Volage, under current over current & dry run protection suitable for the pump described above 1 no Indoor type Upto 6 HP pumps	No	9882.85	Rupees Nine Thousand Eight Hundred Eighty Two and Eighty Five Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
E6	1.00	Providing,supplying to work site, Submersible Pump Set of 150mm dia suitable for bore well and confirming to IS 80342000; 3Phase , SS Bowl & Impeller with Low volt Motor as per specifications,as per necessary ammendments and instructions of engineer incharge of work. 3.00 HP - 120 LPM @ 55 m = 5 STG Outlet Dia - 2.00"	each	31160.11	Rupees Thirty One Thousand One Hundred Sixty and Ten Paise Only
E7	81.73	Providing 15 mm cement plaster on the rough side of single or half brick wall of mix 1:4 (1 cement: 4 fine sand) including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge.	Sqm	275.53	Rupees Two Hundred Seventy Five and Fifty Two Paise Only
E8	221.39	Providing half nosing for 40mm thick granite slab using required machinery including cost and conveyance of all materials, labour for all items of work, HOM etc., complete as per specification	m	392.69	Rupees Three Hundred Ninety Two and Sixty Eight Paise Only
E9	40.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge. External work 40mm nominal dia pipes	m	521.06	Rupees Five Hundred Twenty One and Five Paise Only
E10	2.00	Providing and fixing C.P. brass shower rose with 15 or 20 mm inlet : 10mm diameter	Nos.	224.42	Rupees Two Hundred Twenty Four and Forty Two Paise Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
E11	2.00	Supplying ...litres capacity vertical/horizontal type wall mounting Electrical water heater with 22 SWG copper/SS sheet metal inner Container tinned inside and anticorrosive paint outside and 20 SWG M.S. sheet metal outer cover filled with glass wool between inner and outer container for thermal insulation complete. The inlet and outlet pipes so arranged that water flow inside results in water to flow out from the inner container without turbulence. The Inner container shall have direct immersion type copper tube nickel plate .2KW capacity element with a neon indicator fitted with 20A capacity 25 to 85 degree Centigrade range thermostat. The water heater shall completely be wired with 40/0.0076 inch 3 core copper flexible wire of 1.5 meters length and the outer container provided with heavy gauge brackets for wall mounting. 25Litres	Each	10719.13	Rupees Ten Thousand Seven Hundred Nineteen and Thirteen Paise Only
E12	227.53	Supplying & fixing - flexible LED Strip Light .....W Power consumption in 5mtrs length CCT 6500 degree K, CRI> 70%. efficacy >80 lumen per watt, life> 25000 burning hours and Compliance to IS 10322/IEC 60598, LM 79 & LM 80. The LED are driven by HF electronic driver non integrated, with PF > 0.95, power loss should < 5% of lamp wattage., short circuit & open circuit protection to be integrated in the circuit, THD less than 20%, Life as per LM 79. The operating input voltage should be between 130 to 275 volts. BIS Approved with 2 years Warranty against any manufacturing defect working under standard electrical condition.	m	1804.87	Rupees One Thousand Eight Hundred Four and Eighty Seven Paise Only
E13	4.00	Supplying of 1440rpm heavy duty exhaust fan with bracket blades suitable to operate on 230V 50Hz, AC Supply complete. 12" Sweep (300mm)	Each	3026.97	Rupees Three Thousand Twenty Six and Ninety Seven Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
E14	14.00	Supplying & fixing of retrofit type - LED bulb.....W with OPAL acrylic diffuser comprising of LED source with CCT 6500 degree K, CRI> 70%. efficacy >80 lumen per watt, life> 25000 burning hours and Compliance to IS 10322/IEC 60598, LM 79 & LM 80. The LED are driven by HF electronic driver integrated in the system, with PF > 0.95, power loss should < 5% of lamp wattage., short circuit & open circuit protection to be integrated in the circuit, THD less than 20%, Life as per LM 79. The operating input voltage should be between 130 to 275 volts. BIS Approved and Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition. 9W, 6500K	Each	161.60	Rupees One Hundred Sixty One and Sixty Paise Only
E15	312.06	Acrylic Synthetic Paint for Basket Ball Court and PVC Flooring for Badminton Court, - Providing and Laying of ITF Certified 5 layers of Acrylic Synthetic Standard System including primer, Resurfacer and Approved colour and Line marking as per international standard. - Providing and Laying of PVC Sports Flooring of 6.5mm thick as per direction of Engineer in Charge. - Providing and Laying of Foam of 8.00 mm thick beneath PVC Sports Flooring as per direction of Engineer in Charge.	Sqm	3750.13	Rupees Three Thousand Seven Hundred Fifty and Thirteen Paise Only
E16	22.33	Providing and Installing mirror, including cost of all materials like plywood, gum, screw, beeding etc., and all lead & lift, transportation and labour charges. The cost also includes all applicable taxes., complete as per direction of engineer in charge.	Sqm	19392.00	Rupees Nineteen Thousand Three Hundred Ninety Two Only
E17	676.97	Providing and fixing Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	kg	122.21	Rupees One Hundred Twenty Two and Twenty One Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

No	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
E18	79.20	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in- charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.) including cost of materials, labour, usage charges of machinery complete as per specifications and as per directions of the Engineer-in-Charge.	kg	555.50	Rupees Five Hundred Fifty Five and Fifty Paise Only
E19	1440.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100v grade, multistrand Copper with low conductor resistance single core cable in open or concealed system of wiring with specified IS-694:comfirming to latest amendments. 4 Sqmm	m	59.59	Rupees Fifty Nine and Fifty Nine Paise Only
E20	195.00	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. for: PVC pipes 110mm dia., 6 kg/sqcm & class 3	m	429.78	Rupees Four Hundred Twenty Nine and Seventy Seven Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda & D	
				In figures	In words
E21	108.00	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. for: PVC pipes 140mm dia., 6 kg/sqcm & class 3	m	618.48	Rupees Six Hundred Eighteen and Forty Eight Paise Only
E22	1.00	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. for: PVC pipes 140mm dia., 6 kg/sqcm & class 3	Each	383062.70	Rupees Three lakh Eighty Three Thousand Sixty Two and Seventy Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Modified Quantity	Item Name	Unit	Approved Rates by Sri. Venkatesh Gowda S D	
				In figures	In words
E23	1.00	Supplying PVC ringtite pipes conforming to IS 4985:2000 with latest amendments and conveying to worksite, rolling and lowering into trenches, laying true to line and level and perfect linking at joints, testing and commissioning, including loading unloading at both destinations and cuts of pipes wherever necessary including jointing of PVC pipes and specials (excluding cost of specials) with jointing of approved type, with all labour with all lead & lift including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excavation etc. complete and giving necessary hydraulic test to the required pressure as per ISS (Contractor will make his own arrangements for procuring water for testing) etc. for: PVC pipes 140mm dia., 6 kg/sqcm & class 3	Each	347154.17	Rupees Three lakh Forty Seven Thousand One Hundred Fifty Four and Seventeen Paise Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone